

उदय प्रताप कालेज, वाराणसी

(स्वायत्तशासी संस्था)
नैक पुनर्मूल्यांकित 'B' ग्रेड



Udai Pratap College, Varanasi

(Autonomous Institution)
NAAC Re-accredited 'B' Grade

College with Potential for Excellence, DST-FIST & DBT-Star College

Mob. No 09450538242 Phone: 0542-2282399, Fax- 0542-2282399, email: principalupc@gmail.com, Website: www.upcollege.org

पत्रांक

/निर्माण/ 2020-2021

दिनांक 14.12.2020

कोटेशन सूचना

सर्वसाधारण को सूचित किया जाता है कि उदय प्रताप कालेज नवीन गर्ल्स छात्रावास के मरम्मत कार्य हेतु कोटेशन दिनांक 16.12.2020 तक आमन्त्रित की जाती है। कोटेशन दिनांक 18.12.2020 को अपराह्न 1.00 बजे प्राचार्य कार्यालय, उदय प्रताप कालेज, वाराणसी में कोटेशनदाताओं के समक्ष खोली जायेगी। न्यूनतम दर पाये जाने वाले फार्म को कार्य करने हेतु आवंटित किया जायेगा। कोटेशन निरस्त करने के लिए समस्त अधिकार प्राचार्य, उदय प्रताप कालेज, वाराणसी के पास निहित होगा।

डॉ० (जी०एस० राठौर)
प्राचार्य

BILL OF QUANTITY


Name of Work – Udai Pratap Degree College New Girals Hostel repairing work

Date of Quotation- 16-12-2020

Date of opening Quotation- 18-12-2020

Period of completion of work- One Month

| S. No. | Items and S.I. No. | Qty. | Unit | Rate |
|--------|---|--------|------|---------|
| 1. | S/fixing mosquito proot jaal having mesh each of 24 BWG wire heavy quality 25 X5 mm plat iron i/c all babour material etc complete PWD-S ₅₂ block-A | 9.96 | Sqm. | 660.00 |
| 2. | Scraping old white colour wash including disposal etc. PWD-708 | 283.83 | Sqm. | 8.50 |
| 3. | Coloure washing (two coat) i/c all labour material etc complete PWD-675 | 283.83 | Sqm. | 16.00 |
| 4. | Patch repairing 1:4 plaster cement c.sand i/c all labour material etc. complete PWD-584 | 14.19 | Sqm. | 129.00 |
| 5. | Patch white based putty of smooth surface etc complete work DSR-13.80 | 14.19 | Sqm. | 108.04 |
| 6. | P/Fixing 4mm thick window glass with putty etc. complete block-B | 14.85 | Sqm. | 470.00 |
| 7. | Repairing plumbing work etc. | 1.00 | Job | 8500.00 |
| 8. | 40mm cement concrete roof top slab flooring 1:2:4 cement cores sand store aggregate finished with floating of neat cement slury with water proofing camical all labaur material etc complete DSR-11.30 Block No-B | 238.28 | Sqm. | 498.35 |
| 9. | Dismantling in floor tiles in toilet Block –B etc. | 24.84 | Sqm. | 45.00 |
| 10. | p/laying 600 X 600mm vitrified floor tiles 1:4 cement cores sand all labuor material in toilet Block etc. complete (G.F.) Toilet Block-B | 28.84 | Sqm. | 1150.00 |


जय कुमार
कनिष्ठ अभियंता
उदय प्रताप शिक्षा समिति
वाराणसी