

उदय प्रताप कालेज, वाराणसी

(स्वायत्तशासी संस्था)

नैक पुनर्मूल्यांकित 'B' ग्रेड



Udai Pratap Colleg Varanasi

(Autonomous Institution)

NAAC Re-accredited 'B' Grade

College with Potential for Excellence, DST-FIST & DBT-Star College


Mob. No 9412677448 Phone: 0542-2282399, Fax- 0542-2282399, email: principalupc@gmail.com, Website: www.upcollege.org

दिनांक 11.01.2022

टेण्डर सूचना

सर्वसाधारण को सूचित किया जाता है कि कालेज परिसर स्थित पैवेलियन पर ब्वाय टायलेट, गर्ल्स टायलेट एवं वीआईपी. टायलेट के निर्माण हेतु पंजीकृत ठेकेदारों से मुहरबन्द टेण्डर दिनांक 20.01.2022 को अपराह्न 3.00 बजे तक प्राचार्य, उदय प्रताप कालेज, वाराणसी के कार्यालय में आमंत्रित किया जाता है, जो उसी दिन अपराह्न 4.00 बजे उपस्थित ठेकेदारों एवं निर्माण समिति के सदस्यों के समक्ष खोला जायेगा। टेण्डर प्रपत्र के साथ कार्य की प्रकृति, मात्रा लागत विवरण संलग्न है। ठेकेदार के पास किसी भी सरकारी संस्था में कार्य करने का पूर्व अनुभव आवश्यक है। 10 प्रतिशत धनराशि जमानत/धरोहर धनराशि बैंक ड्राफ्ट/किसान विकास पत्र/राष्ट्रीय बचत प्रमाण-पत्र प्राचार्य, उदय प्रताप कालेज, वाराणसी के नाम बन्धक होगा। अधिकृत ठेकेदार/फर्म का पैन नम्बर व टिन नम्बर का स्पष्ट उल्लेख अनिवार्य है। बिना जमानत/धरोहर धनराशि एवं सशर्त टेण्डर पर विचार नहीं किया जायेगा।

एक या उससे अधिक टेण्डर को निरस्त करने का पूर्ण अधिकार प्राचार्य, उदय प्रताप कालेज, वाराणसी के पास निहित होगा।


डॉ० (धर्मेन्द्र कुमार सिंह)
प्राचार्य

Udai Pratap College, Varanasi (UP).

Computation Sheet

Name of work : Boy Toilet, Girl Toilet, VIP Toilet, Construction of All Civil Work, Plumbing Work, Painting Work, WaterProofing Work, drain pipe work, Complete of Job. at Udai Pratap College, Varanasi (UP).

S.No.	DESCRIPTION OF ITEMS	UNIT	TENTATIVE QTY	RATE		
1	Excavation in foundation in ordinary soil (loamclay or sand) including lift up to 1.5m and lead up to 30m. and including filling watering and ramming of excavated earth into the space between the building and the sides of foundation trenches or into the plinth and removal and disposal of surplus earth as directed by the Engineer in charge up to a distance of 30m. from the foundation trenches including all T&P phowarah and					
2	PAVEMENT CEMENT CONCRETE construction of plain cement concrete pavement thickness as per design, over a prepared sub base with 43 grade cement or any other type as per clause M 15 (grade) (1:2:4) 1 cement, 2 coarse sand 4 aggregate					
3	RCC work laying in position specified grade of reinforced cement concrete, Slab including the cost of centering, shuttering, finishing and excluding reinforcement - Above plinth level upto fifth floor level in 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size					

4	laying cement concrete in 1:5:10 (1 Cement : 5 Coarse sand : 10 graded stone aggregate 40 mm nominal size) including supply of all materials, labour and T&P etc. required for completion of work and curing complete, including cost of form work. In Foundation and floors. (274) Same as above but in 40mm Brick Ballast.	Sum	95			
5	Class-150 brick work in 1:3 cement and Coarse sand mortar in foundation and plinth including supply of all materials, labour and T&P etc. required for proper completion of the work. (DSR Sl.No.6.8)					
6	Mild steel or iron work in plain work such as reinforced concrete or reinforced brick work (When not included in and an over all rates) brought to required shape as necessary including bending for proper completion of the work and excluding the supply of steel and its wastage Bend, hooks and authorized over lapping shall be measured upto floor to level. (1) 6mm (2) 10mm to 12mm , 16mm					
7	plaster on exterior walls and outer wall height upto 12 metre above ground level, in two layers, under layer 12 mm cement plaster 1:4 (1 cement : 4 coarse sand), furrowing the under layer with scratching tool, applying cement slurry on the under layer @ 2 Kg of cement per square metre, of Engineer-in- charge.					
Total Amount				0	0	0

8	plumbing works Girl toilet and boy toilet VIP Guest toilet plumbing works all workes etc. directed by the Engineer in charge.	NO.	6.00			
9	Tiles Works Girl toilet and boy toilet VIP Guest toilet Flooring Tiles and Wall Tiles all workes etc. directed by the Engineer in charge.	Sum	385.00			
10	Electrical Works, Girl toilet and boy toilet VIP Guest toilet, Electrical all workes etc. directed by the Engineer in charge.	Sum	95.00			
11	Painting Works Girl toilet and boy toilet VIP Guest toilet Painting Works and Wall Putti all workes etc. directed by the Engineer in charge.	Sum	585.00			
<u>Total Amount</u>				0.00	0.00	0.00

PAYMENT TERMS:

- 1 (i) 25% Payment after Works complete. 30% Works footing ,plinth beam, and column slab level.
- 2 (ii) 50% Payment after Works Complete. 60% Works sleb, plaster, in and outer sid ,Tiles Works Wall and Flooring, door fitting , stair
- 3 (iii) 80% payment after Works Complete 90% Works ,plumbing Works and Waterproofing, electrical Works, all testing
- 4 (iv)90% Payment after Works Complete 100% Woeks ,Wall putty painting and all Works tasting. All complete fo Works
- 5 (v)10% payment after 10 deyse.

